

## J5/J6/J8

Labor shall be based on the following:

### Construction

- Assemble in accordance to Construction Specification Drawing and Specifications for Construction
- Tie in conductor/cable
- Any associated labor and temporary material for installation on existing line (i.e. cover up, conductor support, etc)

### Removal

- Any labor necessary to prepare for removal (i.e. cover up, conductor support, etc.)
- Untie Conductor and removal of specified unit
- All Removed Material shall be returned to the District Storeroom in which the project is located

### Replacement

- Removal of Specified Unit including any associated labor and temporary material required for safe removal of Existing Specified Unit (i.e. cover ups, conductor support, etc)
- Installation of New Specified Unit in accordance to Construction Specification Drawing and Specifications for Construction and associated labor for removal of temporary material (i.e. cover up, conductor support, etc.)
- Tie in conductor/cable
- All Removed Material shall be returned to the District Storeroom in which the project is located

## J10

Labor shall be based on the following:

### Construction

- Assemble in accordance to Construction Specification Drawing and Specifications for Construction
- Tie conductor in specified unit
- Any associated labor and temporary material for installation on existing line (i.e. cover up, conductor support, etc)

### Removal

- Untie Conductor and removal of specified unit
- Any labor necessary to prepare for removal (i.e. cover up, conductor support, etc.)
- All Removed Material shall be returned to the District Storeroom in which the project is located

### Replacement

- Removal of Specified Unit including any associated labor and temporary material required for safe removal of Existing Specified Unit (i.e. cover ups, conductor support, etc)
- Installation of assembly unit in accordance to Construction Specification Drawing and Specifications for Construction and associated labor for removal of temporary material (i.e. cover up, conductor support, etc.)
- All Removed Material shall be returned to the District Storeroom in which the project is located

## J11/J13/J17

Labor shall be based on the following:

### Construction

- Assemble in accordance to Construction Specification Drawing and Specifications for Construction
- Secure conductor in deadend shoe
- Any associated labor and temporary material for installation on existing line (i.e. cover up, conductor support, etc)

### Removal

- Remove conductor from deadend shoe and removal of the specified unit
- Any labor necessary to prepare for removal (i.e. cover up, conductor support, etc.)
- All Removed Material shall be returned to the District Storeroom in which the project is located

### Replacement

- Remove conductor from deadend shoe and Removal of the Specified Unit, or portion of, including any associated labor and temporary material required for safe removal of Existing Specified Unit (i.e. cover ups, conductor support, etc)
- Installation of New Specified Unit, or portion of, in accordance to Construction Specification Drawing and Specifications for Construction and any associated labor for removal of temporary material (i.e. cover up, conductor support, etc.)
- Secure conductor in deadend shoe
- All Removed Material shall be returned to the District Storeroom in which the project is located