

M40-1/M40-2

Labor shall be based on the following:

Construction

- Labor for tying conductor to insulator

Removal

- Untying conductors
- Removal of Armor Rod if present
- All Removed Material shall be returned to the District Storeroom in which the project is located

Replacement

- Any labor necessary to prepare for replacement (i.e. de-energizing line, cover-ups, etc.)
- Remove hand tie - replace with appropriate preformed tie
- Replace and Install Armor Rod as required
- All Removed Material shall be returned to the District Storeroom in which the project is located

M40-10

Labor shall be based on the following:

Construction

- Install Aerial Marker on conductor in accordance to manufactures specifications
- Number of and spacing will be provided in accordance to the application

Removal

- Remove Aerial Marker
- All Removed Material shall be returned to the District Storeroom in which the project is located

Replacement

- Any labor necessary to prepare for removal (i.e. cover-ups, de-energizing line, grounds, etc.)
- Removal of Aerial Marker
- Install new Aerial Marker on conductor in accordance to manufactures specifications – on a one for one replacement unless otherwise directed
- All Removed Material shall be returned to the District Storeroom in which the project is located