


**NOTES:**

1. BOND ALL CONCENTRIC NEUTRALS TOGETHER USING APPROPRIATE NUMBER OF GROUND CLAMPS.
2. PROVIDE SUFFICIENT PRIMARY NEUTRAL PIGTAIL AND CABLE SLACK TO PERMIT READY DISCONNECTION OF ELBOW AND MOUNTING ON PARKING STAND.



*Michelle Galloway*  
09/20/2018

ITEM	COMPATIBLE UNIT	QUANTITY	UNIT DESCRIPTION
A	VUM3-1	2	25kV PRIMARY CABLE TERMINAL
B	UM6-4	1	INDICATOR FAULT 1PH 200 MAN RST
C	N/A	AS REQ'D	2001295 - #6 BARE COPPER WIRE - SOLID SD
D	N/A	*2	2000558 - CABLE SEALING KIT (1/0)

**SPECIFY UJ2-4 FOR 25-75kVA XFMRs AND UJ3-4 for XFMRs LARGER THAN 75kVA**

\*DENOTES "GRAB BAG" ITEM.

REV | A | DATE | 09/21/2018 | REVISION | ISSUE FOR CONSTRUCTION | BY | RWC | CHK | EJD | APR | MMG



**MATERIAL SPECIFICATION**

**1Ø PADMOUNT TRANSFORMER FEED THROUGH**

drawn:	approved:	date:	101-002
RWC	MMG	08/31/2018	